TOWN OF WHITESTOWN BOONE COUNTY, INDIANA

STANDARD DETAILS



ADOPTED AUGUST 14, 2012

UPDATED _____ MAY, 2015

TOWN OF WHITESTOWN - STAFF

TOWN MANAGER - DAX NORTON

PUBLIC WORKS DIRECTOR - JASON LAWSON

TOWN CLERK - AMANDA ANDREWS

POLICE CHIEF - DENNIS ANDERSON

FIRE CHIEF - JOSH WESTRICH

TOWN OF WHITESTOWN - COUNCIL

PRESIDENT - ERIC MILLER

MEMBER - SUSAN AUSTIN

MEMBER - KEVIN RUSSELL

MEMBER - DAWN SEMMLER

MEMBER - JULIE WHITMAN

TOWN HALL - (317) 769-6557 UTILITY OFFICE - (317) 733-8584



	DRAWING INDEX									
SHT. NO.	DRAWING TITLE									
	COVER									
1	STANDARD DETAILS FOR WATER MAINS									
2	STANDARD DETAILS FOR WATER MAINS									
3	STANDARD DETAILS FOR WATER MAINS									
4	STANDARD DETAILS FOR SANITARY SEWERS									
5	STANDARD DETAILS FOR SANITARY SEWERS									
6	STANDARD DETAILS FOR SANITARY SEWERS									
7	STANDARD DETAILS FOR STREETS									
8	STANDARD DETAILS FOR STREETS									
9	STANDARD DETAILS FOR ROADS									
10	LIFT STATION SITE LAYOUT AND ELECTRICAL DIAGRAM									
11	LIFT STATION GENERAL CONFIGURATION									

FILE NAME: L:\AutoCAD Resources\Indy Sanitary\Client Standards\Whitestown — 120409\Details

2. ALL FITTINGS TO BE DUCTILE IRON, CLASS 350 (AWWA C153) MECHANICAL JOINT (AWWA C111) WITH RESTRAINED OR LOCK JOINT. THRUST BLOCKS NOT ACCEPTABLE.


- 3. TERMINATE LOCATION WIRE AT WATER MAIN GATE VALVE WITH TERMINAL CONNECTION.
- 4. LOCATION WIRE SHALL BE COLORED BLUE FOR WATER AND GREEN FOR SANITARY SEWER, JOINTS IN LOCATE WIRES SHALL BE OVERHAND KNOTTED AND SOLDERED THEN COVERED WITH A WATER PROOF SEAL.
- 5. ALL NEW OR REPAIRED WATER MAIN SHALL BE DISINFECTED IN ACCORDANCE WITH AWWA 651 AND HYDROSTATIC TESTED IN ACCORDANCE WITH AWWA C600 PRIOR TO BEING PLACED IN SERVICE.
- 6. VALVES AND FIRE HYDRANTS SHALL BE PROVIDED AT MAXIMUM 600' INTERVALS ALONG WATER MAINS.
- 7. ALL WATER MAINS PROVIDING FIRE SERVICE SHALL BE MIN. 6" DIAMETER.
- 8. IN UNDEVELOPED AREAS, WATER MAIN MARKER POSTS MAY BE REQUIRED AT 400' INTERVALS OR AS REQUIRED FOR LINE OF SIGHT. HANDLEY INDUSTRIES OR EQUAL.

WATER METER SETTING SCHEDULE									
STYLE	SINGLE 5/8"	DOUBLE 5/8"	SINGLE 3/4"	DOUBLE 3/4"	SINGLE 1"	SINGLE 1 1/2"-2"			
INLET	3/4" COMP.	1" COMP.	3/4" COMP.	1" COMP.	1" COMP.	1 1/2"-2" COMP.			
OUTLET	3/4" COMP.	3/4" COMP.	3/4" COMP.	3/4" COMP.	1" COMP.	1 1/2"-2" COMP.			


WATER METER AND SERVICE NOTES:

- 1. ALL 1"-2" TAPS TO PVC PIPE WILL USE A SMITH BLAIR #317 STYLE EPOXY COATED DUCTILE IRON SERVICE SADDLE WITH DOUBLE STAINLESS STEEL BANDS OR APPROVED EQUAL. DUCTILE IRON PIPE MAY BE DIRECT TAPPED. TAPS SHALL BE ANGLED UP 45° AT CONNECTION TO MAIN.
- 2. MINIMUM 6" OF WASHED AGGREGATE WILL BE USED UNDER ALL METER PITS FOR DRAINAGE.
- 3. ALL METERS LARGER THAN 2" WILL BE SUPPLIED BY THE CONTRACTOR, FROM TOWN'S VENDOR.
- 4. ALL TUBING CONNECTIONS WILL BE DONE WITH MUELLER OR McDONALD BRASS COMPRESSION FITTINGS.
- 5. ALL CORPORATION AND CURB STOPS WILL BE MUELLER 300 BALL VALVE OR McDONALD EQUIVALENT.
- 6. ALL RESIDENTIAL CONSTRUCTION REQUIRES THE USE OF DUAL METER INSTALLATIONS WHENEVER POSSIBLE. ANY EXCEPTIONS WILL NEED THE APPROVAL OF THE UTILITY MANAGER
- 7. FINAL GRADE OF METER PIT IS THE SOLE RESPONSIBILITY OF THE DEVELOPER. NO MORE THAN MAX. 12" RISER MAY BE ADDED IN ORDER TO BRING PIT TO GRADE.
- 8. METER PIT LIDS SHALL BE CAST IRON WITH LARGE PENTAGON NUT (MUELLER OR TYLER). METER PIT LIDS SHALL HAVE HOLES FOR RADIO READ ANTENNA MOUNTING (TWO HOLES ON DUAL METER
- 9. ALTERNATE FOR MUELLER WILL BE A.Y. McDONALD BRASS. A LIST OF THOSE SPECIFICATION NUMBERS IS AVAILABLE UPON REQUEST FROM THE TOWN OF WHITESTOWN UTILITY MANAGER.
- 10. THE DEVELOPER SHALL SUBMIT FIXTURE UNIT FLOW AND PRESSURE LOSS CALCULATIONS FOR THE TOWN'S REVIEW AND APPROVAL FOR ANY PLANNED MULTI-FAMILY, COMMERCIAL, OR INDUSTRIAL CONNECTION.

WATER METERS FOR COMMERCIAL MECHANICAL ROOMS INDOOR COMMERCIAL WATER METERS UP TO 2" SHALL HAVE COPPER METER YOKES WITH HORIZONTAL INLET & OUTLET AND LOCKABLE BY-PASS, EQUIVALENT TO MUELLER B-2423-2. LARGER METERS SHALL BE EVALUATED ON A CASE-BY-CASE BASIS, BUT SHALL GENERALLY BE MOUNTED HORIZONTALLY WITH PIPING CONFIGURED SIMILAR TO THE VAULT DETAIL ON SHEET 2. A REMOTE DIGITAL METER READOUT SHALL BE INSTALLED ON THE OUTSIDE OF THE BUILDING TO FACILITATE METER READING. COORDINATE INSTALLATION WITH THE TOWN OF WHITESTOWN. MEANS OF ACCESS FOR THE TOWN SHALL BE PROVIDED



SET TOP FLUSH WITH GROUND OR PAVEMENT ADJUSTABLE C.I. VALVE BOX AS MANUFACTURED BY TYLER -PROVIDE POSI-CAP OR **EQUIVALENT UNDER** OPERATING NUT — **AWWA C509 RESILIENT** SEAL M.J. X M.J. GATE -INSULATED #10 COPPER VALVE (MUELLER A2360) LOCATE WIRE EXTENDED TO BE SAME SIZE AS MAIN UP INTO VALVE BOX CONCRETE BASE FOR GATE VALVES LARGER THAN 12". CONCRETE BASE SHALL BE 1 C.Y. OF - PROVIDE #8 STONE BACKFILL. 2,000 PSI CONCRETE. VALVE SHALL SIT ON 6" BELOW VALVE AND 12" CONCRETE BASE AND VALVE SHALL NOT BE CAST ABOVE BOTTOM OF VALVE BOX INTO CONCRETE. BACKFILL WITH #8 STONE



TYPICAL GATE VALVE & VALVE BOX

NOT TO SCALE

STANDARD FIRE HYDRANT

NOT TO SCALE

SNOWPLOWABLE BLUE REFLECTORS SHALL BE INSTALLED IN CENTER OF ROAD AT ALL FIRE HYDRANTS; PROVIDE TOWN **INSTALL 4X4** WITH AN OPERATING WRENCH AND TRAFFIC DAMAGE REPAIR KIT(S). SEE TOWN SPECIFICATIONS. MARKER POST PAINTED BLUE TO LOCATE 5'-0" DIA (ID) PRECAST CONCRETE CURB STOP -VALVE VAULT W/ FLAT PRECAST CONCRETE TOP SLAB & C.I. MANHOLE FRAME W/ SOLID LID CAST INTO SLAB. MANHOLE FRAME & LID CAST SIMILAR TO FINISHED GRADE **NEENAH R-1737 OR APPROVED EQUAL** 3/4" CORP. STOP W/ CAP - $^{3}\!\!4$ " CORP. STOP W/ CAP MUELLER CURB PE OR D.I.R.J. STOP WITH BOX -4 VALVES REQUIRED AT "CROSS" - WATER MAIN TO BE WATER MAIN -DUCTILE IRON PIPE METER 5' EITHER SIDE OF VAULT •— \ LOCATE CURB STOP 2' FROM PROPOSED METER PIT HDPE SERVICE LINE, 200 PSI MIN. RATING GATE VALVE WITH (CRYSTAL BLUE ENDOT PURE POLY) HANDWHEEL OPERATOR 3 VALVES REQUIRED AT "TEE" BOTTOM OF CONCRETE VAULT TO BE OPEN, - CORP STOP PLACE MINIMUM 6" DEPTH OF WASHED

WATER SERVICE CONNECTION DETAIL NOT TO SCALE

TAPPING SADDLE ON PVC MAIN;

DIRECT TAP ON D.I. MAIN

LOCATE WIRE

EXTENDED INTO


FROM MAIN

METER PIT

WATER MAIN -

LEAK DETECTION METER DETAIL

VALVE DETAILS AT INTERSECTIONS



AGGREGATE FILL IN BOTTOM OF VAULT

METER PIT EASEMENT DIAGRAM

NOT TO SCALE

METER BOX AND METER SETTING


PREGISTER No. 11200431 STATE OF





NWO. NMO

N.T.S.

HEET NO.








- RESTRAINED JOINT

METER ASSEMBLY 3"-10" METER INSTALLATION


RESTRAINED JOINT

NOTES:


- 1. VAULT IS A GENERAL REPRESENTATION ONLY. THE DEVELOPER'S ENGINEER SHALL SUBMIT A SPECIFIC VAULT DETAIL FOR THE PLANNED FACILITY.
- 2. ALL METER ASSEMBLIES SHALL BE SPECIFIED BY THE TOWN OF WHITESTOWN. THE DEVELOPER'S ENGINEER SHALL PROVIDE FIXTURE UNIT FLOW AND PRESSURE LOSS CALCULATIONS FOR THE TOWN'S REVIEW AND ACCEPTANCE TO ALLOW A PROPER METER TO BE SELECTED.
- 3. EACH METER VAULT SHALL BE EQUIPPED WITH A DOOR MOUNTED ELECTRONIC DEVICE FOR USE WITH A RADIO READING SYSTEM.
- 4. ALL FITTINGS SUCH AS BENDS AND TEES SHALL BE PROPERLY RESTRAINED.
- 5. VAULT SIZE TO PROVIDE 12" MINIMUM CLEARANCE FROM ALL PIPING AND FITTINGS.
- 6. PIT/VAULT (NON-TRAFFIC AREA) PIT SHALL BE REINFORCED CAST-IN-PLACE CONCRETE, PRECAST CONCRETE, OR LAID BLOCK. APPLY APPROVED WATERPROOFING AGENT TO INTERIOR AND EXTERIOR OF WALLS. SPECIFICATIONS FOR PITS IN TRAFFIC AREAS SHALL BE DETERMINED BY DESIGN REQUIREMENTS.
- 7. INTERIOR PIPING SHALL BE D.I.F.L.




DEAD ENDS OF TEES



DEAD ENDS OF MAINS



VALVES (NON-DEAD END) 8" AND SMALLER



RESTRAINING VALVES-DETAIL

LENGTH TYPE C BEND STANDARD JOINT HORIZ BEND

STANDARD

LENGTH IN FT. TO BE REST. ON EACH SIDE OF FITTING FOR 4" DI PIPE W/ POLY					LENGTH IN	V FT. T	O BE R	EST. C	N EAC	H SIDE	OF FI	TTING FO	R 12" DI PI	PE W/ PO	LY		
TYPE OF BEND	4" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS	TYPE OF BEND	4" TEE	6" TEE	8" TEE	10" TEE	12" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS
HORIZ. BEND	44	18	10	10	10	53	HORIZ. BEND	28	58	89	116	144	49	21	10	10	152
VERT. BEND			22 UPPER 10 LOWER	11 UPPER 10 LOWER	10 UPPER 10 LOWER		VERT. BEND							63 UPPER 17 LOWER	31 UPPER 10 LOWER	15 UPPER 10 LOWER	

LENGTH IN FT. TO BE REST. ON EACH SIDE OF FITTING FOR 6" DI PIPE W/ POLY									
TYPE OF BEND	4" TEE	6" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS		
HORIZ. BEND	39	66	25	11	10	10	74		
VERT. BEND				31 UPPER 10 LOWER	15 UPPER 10 LOWER	10 UPPER 10 LOWER			
	•				•				

LENGTH IN FT. TO BE REST. ON EACH SIDE OF FITTING FOR 16" DI PIPE W/ POLY											
TYPE OF BEND	4" TEE	6" TEE	8" TEE	10" TEE	12" TEE	16" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS
HORIZ. BEND	19	48	79	105	133	188	63	26	13	10	196
VERT. BEND								82 UPPER 22 LOWER	39 UPPER 11 LOWER	20 UPPER 10 LOWER	

LENGTH IN FT. TO BE REST. ON EACH SIDE OF FITTING FOR 8" DI PIPE W/ POLY										
TYPE OF BEND	4" TEE	6" TEE	8" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS		
HORIZ. BEND	34	62	89	32	14	10	10	97		
VERT. BEND					41 UPPER 12 LOWER	20 UPPER 10 LOWER	11 UPPER 10 LOWER			

LENGTH IN FT. TO BE REST. ON EACH SIDE OF FITTING FOR 20" DI PIPE W/ POLY											
TYPE OF BEND	6" TEE	8" TEE	10" TEE	12" TEE	16" TEE	20" TEE	90° BEND	45° BEND	22 1/2° BEND	11 1/4° BEND	DEADENDS
HORIZ. BEND	27	35	42	50	65	80	55	23	11	10	80
VERT. BEND								45 UPPER 20 LOWER	22 UPPER 10 LOWER	11 UPPER 10 LOWER	

- 1. CONTRACTOR SHALL INSTALL RJDI FITTINGS FOR ALL VERTICAL AND HORIZONTAL BENDS.
- 2. RESTRAINED LENGTHS WERE CALCULATED ASSUMING 54" DEPTH OF BURY, A 2.0 FACTOR OF SAFETY, TYPE 3 TRENCH CONDITIONS, "CL" SOIL CLASSIFICATION, AND 150 PSI HYDROSTATIC TEST PRESSURES. DESIGNER AND CONTRACTOR SHALL VERIFY INSTALLATION CONDITIONS AND MODIFY RESTRAINT LENGTHS AS REQUIRED TO MEET ACTUAL CONDITIONS SUBJECT TO REVIEW BY THE TOWN OF WHITESTOWN.

NOT TO SCALE

RESTRAINT OF BENDS-DETAIL

— STANDARD JOINT

RESTRAINT JOINT TABLES

ALL WATER MAIN APPURTENANCES WITHIN RJDI LIMITS MUST BE RESTRAINED AT EACH JOINT.

REDUCERS, LARGER PIPE DIAMETER IS 8" OR SMALLER - RESTRAINED JOINT RESTRAINED JOINT RESTRAINED JOINT RESTRAINED JOINT REDUCERS, LARGER PIPE DIAMETER IS 12" OR LARGER RESTRAINING REDUCERS-DETAIL → TOTAL LENGTH OF RESTRAINT → STANDARD JOINT

(4) DISMANTLING JOINT

RESTRAINED JOINT

ROMAC DJ400 OR DJ405. (SET AT NOMINAL LENGTH)

RESTRAINED JOINT

RESTRAINT LENGTH OF RESTRAINT SAME AS FOR 90° BENDS & DEAD ENDS. SEE CONSTR. STD. "LENGTH AND METHOD OF RESTRAINT"

> RESTRAINT OF TEES-DETAIL NOT TO SCALE

SEE CONSTR. STD. FOR "LENGTH AND

METHOD OF RESTRAINT"

PREGISTER No. 11200431 STATE OF





MAINS

里

TOWN

OF

NWO.

AND,

N.T.S.

- REFER TO DETAIL AT

TYPE "A" MANHOLE

TRAFFIC BEARING

PCC MANHOLE LID

- ROUND "O" RING RUBBER GASKET

OR EQUAL) PREFORMED GASKET

BETWEEN ALL PRECAST SECTIONS

UNDISTURBED SOIL W/

OF 1500 LBS./SQ. FT.

MIN. BEARING CAPACITY

PLUS 1/2" EXTRUDABLE (KENT SEAL

FOR ADDITIONAL

INFORMATION

---||FLOWY

SLOPE AWAY FROM GRINDER PUMP

DISCHARGE PIPE

1.25" HDPE

LENGTH

VARIES

FROM GRINDER PUMP —

SECTION A-A

N.T.S.

HEET NO.

IN UNPAVED AREAS, SET TOP OF CASTING TEMPORARY SILT FENCE TO BE MIN. 3" ABOVE SURROUNDING ELEVATION INSTALLED AROUND ALL AND SLOPE AREA AWAY TO PREVENT MANHOLES UNTIL FINAL GRADING SURFACE WATER INFILTRATION. TYPICAL AND SURFACE RESTORATION HAS FOR ALL SAN. SEWER MANHOLE TYPES. BEEN COMPLETED IN AREA SO - C.I. MANHOLE THAT MANHOLES ARE NOT BURIED FRAME & COVER BY SUBSEQUENT GRADING WORK --BUTYL & PLASTIC WRAP ALL BARREL SECTION JOINTS AND CHIMNEY RISERS ON THE PRECAST CONCRETE OUTSIDE OF MANHOLE; GRADE RINGS — CONSEAL CS-212 OR EQUAL 🚤 2'-0" MIN. 🔹 - 1/2" EXTRUDABLE PRECAST CONCRETE MANHOLE PREFORMED GASKET SEAL CONFORMING TO ASTM C-478 W/MONOLITHIC BOTTOM SECTION -MANHOLE STEPS PER SPECS - BUTYL & PLASTIC WRAP ALL ROUND "O" RING RUBBER GASKET, BARREL SECTION JOINTS AND PLUS 1/2" EXTRUDABLE (KENT SEAL CHIMNEY RISERS ON THE OR EQUAL) PREFORMED GASKET OUTSIDE OF MANHOLE; BETWEEN ALL PRECAST SECTIONS -CONSEAL CS-212 OR EQUAL - 4'-0" MIN. DIAMETER * -- SHAPE TO FORM SMOOTH GROUT CAP AT FLOW FLOW CHANNEL POURED CHANNEL, TYP. — UP TO CROWN OF PIPE FLOW -

> TYPE "A" MANHOLE STANDARD PRECAST MANHOLE

* DIAMETER SHALL BE LARGE ENOUGH TO

ACCOMMODATE CONNECTED PIPING

4" MIN.

UNDISTURBED SOIL W/ MIN.

BEARING CAPACITY OF

1500 LBS./SQ. FT.

FLOW SHAPE TO FORM EASY FLOW CHANNEL -CUT OFF PIPE SQUARE @ WALL CONCRETE BENCH WALL SLOPED TO DRAIN FLOW -INSIDE OF ALL SAN. MANHOLE TYPES SHALL BE FREE OF EXCESS MORTAR, MASTIC AND OTHER LIKE MATERIAL

FLOW

STANDARD MANHOLE

BENCH WALL

NOT TO SCALE

ALOK CONNECTOR CAST


MINIMUM 4" #8 STONE. MINIMUM


4" #2 STONE OVER FILTER FABRIC

INTO NEW MANHOLE ---

BASE LEVELING COURSE

IN WET CONDITIONS. -





CASING END SEAL DETAIL

NOT TO SCALE

STEEL CASING PIPE ----- CASING PIPE SPACER WITH PLASTIC RUNNERS AND STAINLESS STEEL CLAMP MANUFACTURED BY "CASCADE WATERWORKS MFG." OR EQUAL CARRIER PIPE

NOTE: CONFIGURE CASING SPACERS PER MFGR. RECOMMENDATIONS FOR GRAVITY CARRIER PIPES TO CORRECT FOR GRADE.

CENTERING CARRIER PIPE WITH CASING SPACER (PRESSURE PIPES)


MANHOLES SHALL BE VACUUM TESTED IN ACCORDANCE WITH ASTM C1244TAILS UTILIZE ONE SECTION OF - MANHOLE STEPS D.I. PIPE OUTSIDE OF DROP PER SPECS CONNECTION TO MANHOLE — D.I. M.J. COUPLING BUTYL & PLASTIC WRAP ALL — ALOK CONNECTOR CAST BARREL SECTION JOINTS AND ─ PVC MAIN INTO NEW MANHOLE CHIMNEY RISERS ON THE OUTSIDE OF MANHOLE; CONSEAL CS-212 OR EQUAL → FLOW DROP PIPE AND FITTINGS TO BE — 4'-0" MIN. DIAMETER * -SAME SIZE AND MATERIAL AS SHAPE TO FORM SMOOTH -MAIN SEWER LATERAL FLOW CHANNEL POURED UP TO CROWN OF PIPE BASE LEVELING COURSE ─4" MIN. ENCASEMENT COVER MINIMUM 4" #8 STONE. MINIMUM 6" MIN. 4" #2 STONE OVER FILTER FABRIC IN WET CONDITIONS.— 100 PSI FLOWABLE FILL ENCASEMENT OR PRECAST CONCRETE ENCASEMENT UNDISTURBED SOIL W/ MIN. BEARING CAPACITY OF 1500 LBS./SQ. FT. * DIAMETER SHALL BE LARGE ENOUGH TO ACCOMMODATE CONNECTED PIPING TYPE "B" MANHOLE OUTSIDE DROP MANHOLE CONNECTION

- REFER TO DETAIL AT

TYPE "A" MANHOLE

FOR ADDITIONAL

INFORMATION



CURB STOP ASSEMBLY DETAIL

TABLE OF STEEL CASING SIZES									
CASING DIAMETER IN INCHES	WALL THICKNESS (WITH PROTECTIVE COATING) IN INCHES	WALL THICKNESS (WITHOUT PROTECTIVE COATING) IN INCHES							
12"	0.188"	0.250"							
16"	0.219"	0.281"							
18"	0.250"	0.312"							
20"	0.281"	0.344"							
24"	0.312"	0.375"							
30"	0.406"	0.469"							
36"	0.469"	0.532"							

NOT TO SCALE

- 2. CASING SPACERS REQUIRED. MAXIMUM 10'-0" SPACING FOR DUCTILE IRON CARRIER PIPES. MAXIMUM SPACING FOR PVC CARRIES PIPES SHALL BE 6'-0". FOLLOW MANUFACTURER'S RECOMMENDATIONS FOR PLACEMENT AND SPACING.
- 3. THE INSIDE DIAMETER OF THE CASING SHALL BE A MINIMUM OF SIX (6) INCHES LARGER THAN THE LARGEST DIAMETER OF THE CARRIER PIPE JOINT.
- CONTACT SPECIFIC RAILROAD FOR REQUIREMENTS.

/ INSTALL 1/2"Ø EXTRUDABLE ← 34" OR 36" O.D. ← PREFORMED GASKET MATERIAL IN EACH KEYWAY (SEE DETAIL) INTERIOR SURFACE OF MANHOLE RECEIVING FORCEMAIN FLOW AND NEXT TWO DOWNSTREAM MANHOLES SHALL RECEIVE INTERIOR EPOXY RECONSTRUCT COATING BY TOWN-APPROVED MANF. **BENCH WALLS** 30 1/2"Ø (NOTE: SHAPE TO -PRECAST CONCRETE ---FORM SMOOTH ADJUSTING RING OR CORE DRILL OPENING -FLOW CHANNEL FLANGE OF CASTING POURED UP TO CROWN OF PIPE) PROPOSED SANITARY SEWER OR FORCEMAIN -PLAN VIEW ⊿ 4" MIN. NOMINAL 1/2" BUTYL FLEXIBLE BOOT CONNECTOR ✓ . RUBBER BASE EXTRUDABLE KOR-N-SEAL OR TOWN 30 1/8"Ø PREFORMED GASKET APPROVED EQUAL — MATERIAL (TYP.) — - EXISTING MANHOLE RISER RING THICKNESS 4" -12" OUTSIDE DIA. 34" OR 36"

BUTYL & PLASTIC WRAP ALL

CONSEAL CS-212 OR EQUAL

OUTSIDE OF MANHOLE;

ALOK CONNECTOR CAST

INTO NEW MANHOLE -

BASE LEVELING COURSE

IN WET CONDITIONS. -

MINIMUM 4" #8 STONE. MINIMUM

4" #2 STONE OVER FILTER FABRIC

LOCATE WIRE (TYP.) -

EXISTING FORCEMAIN

FLOW

BARREL SECTION JOINTS AND CHIMNEY RISERS ON THE

MANHOLE STEPS PER SPECS

FLOW -> -

2'-0" MIN

TYPE "C" MANHOLE SHALLOW MANHOLE LESS THAN 5'

CURB STOP ASSEMBLY

(SEE DETAIL, THIS SHEET)

STOP

─ DOUBLE BOLT SS TAPPING SADDLE; SMITH BLAIR #372 STYLE OR EQUAL

1. GRINDER PUMP INSTALLATION SHALL BE PER

2. TAP TO BE COMPLETED BY CONTRACTOR. TOWN

TO WITNESS TAP. 48 HOURS NOTICE REQUIRED.

GRINDER PUMP

FORCEMAIN TAP DETAIL

MANUFACTURER'S RECOMMENDATIONS


54" MIN. DEPTH (TYP.) - BENCH

PRECAST ADJUSTING RING

GASKET DETAIL

- 1. CASING SHALL BE WELDED STEEL PIPE, NEW AND UNUSED MATERIAL IN ACCORDANCE WITH ASTM A-139; MINIMUM YIELD STRENGTH = 35,000 PSI.
- 4. THE ABOVE GIVEN CASING SIZES DO NOT APPLY TO RAILROAD CROSSINGS.


EXISTING MANHOLE CONNECTION DETAIL



MEL R. CUZ **★** 11200431 STATE OF IN ESSIONALET

Ш S

ANIT



3. CONTRACTOR MAY SUPPLY GREASE TRAP AS MANUFACTURED BY ZURN SERIES Z-1170 OR JAY R. SMITH MANUFACTURING COMPANY SERIES 8000 IF INTERIOR INSTALLATION UTILIZED.

2. EXTERIOR INSTALLATION MUST BE CONCRETE. STEEL GREASE

UTILIZING 4000 PSI CONCRETE. STRUCTURE SHALL BE DESIGNED

4. GREASE TRAPS MUST BE SIZED ACCORDING TO THE INDIANA STATE BOARD OF HEALTH BULLETIN S.E. 13, "ON-SITE WATER SUPPLY AND WASTEWATER DISPOSAL FOR PUBLIC AND COMMERCIAL ESTABLISHMENT" SECTION 501 "GREASE TRAPS" AND PER LOCAL REQUIREMENTS OR CODES. THE SIZING METHOD FOR ALL STRUCTURES MUST BE APPROVED BY THE TOWN.

- 5. SHOP DRAWINGS MUST BE SUBMITTED TO THE UTILITY ENGINEER FOR REVIEW AND APPROVAL.
- 6. TOP OF CASTING SHALL EXTEND 3" MIN. ABOVE FINISHED GRADE.
- 7. SAMPLE BOX SHALL BE PER TOWN STANDARDS.

1. GREASE TRAP SHALL CONFORM TO ASTM 858

TO SUPPORT LOADING IN PLANNED LOCATION.

TRAPS SHALL ONLY BE INSTALLED INSIDE BUILDING.

8. INTERIOR PIPING SHALL BE 6" (MIN.) PVC.

NOTES:

GREASE TRAP DETAIL

BY AN O-RING GASKET PLUS LIQUID DEPTH 30" MIN. TO MASTIC (ROPE) CONFORMING 78" MAX TO ASTM C990. CONTRACTOR SHALL GROUT ALL INTERNAL MANHOLE JOINTS WITH NON-SHRINK GROUT. -±0.66D - A-LOK CONNECTOR CAST INTO STRUCTURE (TYP. ALL PIPE PENETRATIONS). NO PENETRATIONS WILL BE PERMITTED WITHIN 6" OF INTERNAL OR EXTERNAL CLEAN SAND BACKFILL TO INFLUENT AND EFFLUENT PIPES -- STAINLESS STEEL SUPPORT BRACKET 6" MIN. CRUSHED NO. 8 STONE MAT FOR LRVELING AND SUPPORT NO. 2 STONE AS REQUIRED FOR UNSTABLE SOIL CONDITIONS

 STANDARD MANHOLE FRAME AND COVER MANHOLE STRUCTURE. BUTYL & PLASTIC WRAP ALL BARREL SECTION JOINTS AND CHIMNEY RISERS ON THE OUTSIDE OF MANHOLE; CONSEAL CS-212 OR EQUAL. ROUND "O" RING RUBBER GASKET, PLUS 1/2" EXTRUDABLE (KENT LOCATE WIRE TO BE SEAL OR EQUAL) PREFORMED GASKET BETWEEN ALL PRECAST REACHABLE FROM LID 24" MIN. SECTIONS AND ATTACH TO WALL W/ CLEARANCE - STAINLESS STEEL ANGLE BRACKET SS ANCHORS AND TO SUPPORTS WITH INSULATION STAINLESS STEEL HOOK -BETWEEN DISSIMILAR MATERIALS MAY BE REQUIRED BY THE TOWN ON FORCEMAIN LESS THAN 6" DIAMETER. 2" D-025 S.S. ARI COMBINATION AIR ANCHOR BOLTS TO BE SET IN EPOXY GROUT. ANY NECESSARY HARDWARE RELEASE VALVE IS TO BE S.S. SEE NOTE 3 ----FORCEMAIN PIPE WITH STAINLESS 2" DIA. 1/4 TURN ALL STEEL TAPPING BAND (SMITH BLAIR S.S. BALL VALVE ----A-264 OR EQUAL) FORCEMAIN PIPE — 2" S.S. TUBING — SEAL MANHOLE PIPE W/ RUBBER BOOT TRANSITION COUPLING – D.I. PIPE WITHIN STRUCTURE #8 STONE BASE PLUS 5 FEET EITHER SIDE 6" BELOW STRUCTURE— 6" DEEP - 18" DIAMETER SUMP UNDISTURBED EARTH LOCATED NEAR LID ON ONE SIDE OF FORCEMAIN GROUT TO SLOPE FLOOR TO SUMP - 1/4" PER FT.

NOTES:

1. IF MORE THAN ONE AIR RELEASE VALVE IS INSTALLED WITH A FORCEMAIN, THE DEVELOPER SHALL PROVIDE ONE SPARE AIR RELEASE VALVE TO THE TOWN OF WHITESTOWN.

2. AIR RELEASE VALVES MUST BE INSTALLED AT ALL HIGH SPOTS IN PRESSURE PIPE.

3. THE DESIGN ENGINEER SHALL VERIFY ARV SIZING REQUIRED FOR THE FORCE MAIN SYSTEM BEING PLANNED

AIR RELEASE VALVE VAULT DETAIL

NOT TO SCALE

SLOPE SURROUNDING AREA TO DRAIN AWAY FROM CASTING IN UNPAVED AREAS. SET FLUSH TO PAVEMENT IN PAVED AREAS. —— *24" MIN. DIAMETER INFLUENT PIPE ----- PRECAST CONCRETE ← 6" PROTRUSION STRUCTURE PER ASTM ✓ USE A-LOK RUBBER SEAL AT ALL PIPE CONNECTIONS 6" MIN. 2'-0" MAX. 12" TYP. → 6" MIN. ─ EFFLUENT PIPE - #8 STONE GROUT — - SLOPE INVERT TO DRAIN

STANDARD MANHOLE CASTING


SET RIM 3" ABOVE GRADE AND

WHERE DEPTH OF STRUCTURES EXCEEDS 4'-0", A 4FT. DIAMETER MANHOLE SHALL BE PROVIDED, THE PIPING CONFIGURATION SHALL BE THE SAME. MANHOLE STEPS SHALL BE INCLUDED.

TOWARD OUTLET PIPE

SAMPLE STATION MANHOLE INSTALLATION DETAIL

OWN



SHEET NO.

TWO 13'-6" MOVING LANES WITH NO PARKING LANE AS SHOWN ABOVE. ALTERNATIVE, TWO 11'-0" MOVING LANES WITH ONE 8'-0" PARKING LANE.

LOCAL STREET OR CUL-DE-SAC

NOT TO SCALE

NOTE: PEDESTRIAN RAMPS AT INTERSECTIONS SHALL MEET A.D.A. (AMERICAN DISABILITY ACT) SPECIFICATIONS.

SETBACK DIST. AS PER SETBACK DIST. AS PER **ZONING ORDINANCE** ZONING ORDINANCE 65' RIGHT-OF-WAY SLOPE PAVEMENT SLOPE PAVEMENT 1/4" PER FOOT 5' SIDEWALK -- 10' HMA TRAIL -6" UNDERDRAIN

NOTE: TWO 11'-0" MOVING LANES AND ONE 8'-0" PARKING LANE AS SHOWN ABOVE.

MINOR COLLECTOR STREET

NOT TO SCALE

SETBACK DIST. AS PER SETBACK DIST. AS PER ZONING ORDINANCE ZONING ORDINANCE 75' RIGHT-OF-WAY TURN LANE SLOPE PAVEMENT 1/4" PER FOOT SLOPE PAVEMENT 1/4" PER FOOT 5' SIDEWALK -6" UNDERDRAIN


NOTE:

THREE MOVING LANES WITH NO PARKING LANES AS SHOWN ABOVE. TWO OUTSIDE LANES OF 11'-0" EACH, CENTER LANE 16'-0" TOTAL, 12'-0" TURN LANE WITH 4'-0" DIVING CURB (INTERMITTENT AS NEEDED).

OPTIONAL: ADD 8'-0" OF PAVEMENT FOR EACH PARKING LANE.


NOT TO SCALE

MAJOR COLLECTOR STREET




NOTE: INSTALL 12'-0" MOVING LANES, 10'-0" GRASS MEDIAN WITH OCCASIONAL CENTER TURN LANES AND/OR CROSS-OVERS, NO PARKING LANES AS SHOWN ABOVE. BOULEVARD HAS POTENTIAL TO BECOME FIVE-LANE ARTERIAL IF WARRANTED. OPTIONAL: ADD 8'-0" OF PAVEMENT FOR EACH PARKING LANE.

> MAJOR ARTERIAL STREET NOT TO SCALE



FOUR 12'-0" MOVING LANES, 4'-0" CENTER CURBS, NO PARKING LANES AS SHOWN ABOVE OPTIONAL: ADD 8'-0" OF PAVEMENT FOR EACH PARKING LANE

MINOR ARTERIAL STREET



THIS DRAWING REPRESENTS THE MINIMUM REQUIREMENTS FOR A PUBLIC ROAD ENTRANCE. LARGER AND/OR LONGER ACCELERATION AND DECELERATION LANES MAY BE REQUIRED WHEN DEEMED NECESSARY BY THE TOWN OF WHITESTOWN TO ADEQUATELY SERVE THE ANTICIPATED TYPES AND VOLUMES OF TRAFFIC. LENGTH OF ACCELERATION AND DECELERATION LANES MAY BE MODIFIED WHEN WARRANTED AT THE DISCRETION OF THE PLANNING COMMISSION.

MINIMUM PUBLIC ROAD TO PUBLIC ROAD **ENTRANCE REQUIREMENTS**

NOT TO SCALE

11200431



OF OWN REET I TR I

N.T.S

STANDARD BARRICADE

NOT TO SCALE

WITH 3" RED/WHITE REFLECTORS.


MINIMUM OF 4 PER ROAD -

TRAFFIC CONTROL AND SIGNAGE NOTES:

- 1. THE CONTRACTOR/DEVELOPER SHALL PROVIDE AND INSTALL ALL STREET NAME AND ROAD SIGNS PER CURRENT INDOT STANDARDS AND TOWN OF WHITESTOWN DETAILS. ALL TRAFFIC CONTROL DEVICES SHALL COMPLY WITH THE CURRENT INDIANA MUTCD.
- 2. MATERIALS SHALL BE FREE OF BURRS, PITS AND BLEMISHES. AND SHALL PRESENT A SMOOTH
- 3. SIGN BLANKS SHALL MEET INDOT SPECIFICATIONS UNLESS OTHERWISE SPECIFIED.

CLEAN SURFACE.

- 4. ALL STREET SIGNS SHALL HAVE GREEN BACKGROUND WITH WHITE LETTERS, NUMBERS AND BORDERS ON EXTRUDED ALUMINUM BLADES.
- THE STREET NAME LETTERS TO BE ENGINEER GRADE: 9" BLADES WITH 6" NUMBERS, 6" CAPITAL LETTERS AND 4.5" LOWER-CASE LETTERS ON ALL STREETS.
- STOP SIGNS SHALL BE MIN. 30" HIGH INTENSITY.
- SIGN BOLTS TO BE PER INDOT SPECIFICATIONS. BOLTS SHALL BE THEFT PROOF.
- SPEED LIMIT SIGNS SHALL BE 24"X30" HIGH INTENSITY OR ENGINEER GRADE.
- SIGN POST SHALL BE GALVANIZED U-CHANNEL (3LBS/FT), DRIVEN INTO THE GROUND, NO EXCAVATION SHALL BE DONE TO PLACE SIGNS.
- 10. LARGER SIGNS MAY BE NEEDED FOR ROAD CLASSIFICATIONS GREATER THAN LOCAL PER INDIANA MUTCD REQUIREMENTS.



STREET SIGNAGE DETAILS

NOTE: STREET NAME SIGNS TO

BE LOCATED AT ALL STREETS.

STREET NAME SIGN

NOT TO SCALE

NOT TO SCALE

-R1-1 MIN. 30"X30"

HIGH INTENSITY

12" MIN.

-GRADE


7'-0"±

36" MIN.


-GRADE

12" MIN.

STOP SIGN



CONNECTION TO EXISTING STREETS



ROADWAY IMPROVEMENT REQUIREMENTS AT PRIVATE ENTRANCE:

THE MAIN ROAD SHALL BE RECONSTRUCTED FOR THE ENTIRE LENGTH OF THE PASSING BLISTER AND ACCEL/DECEL LANE IMPROVEMENTS. SAW CUT EXISTING ASPHALT PAVEMENT AT THE LIMITS OF CONSTRUCTION OF THE ACCEL/DECEL LANES AND PASSING BLISTER. ALL EXISTING ASPHALT PAVEMENT SHALL BE REMOVED THROUGH THE LENGTH OF WIDENING. PREPARE SUBGRADE FOR NEW PASSING BLISTER, ACCELERATION & DECELERATION LANES, AND MAIN ROADWAY ACCORDING TO THE REQUIREMENTS OF THE TOWN OF WHITESTOWN STANDARD DETAILS.

ASPHALT PAVING OF THE PASSING BLISTER AND ACCELERATION AND DECELERATION LANES SHALL MEET THE MINIMUM REQUIREMENTS OF THE TOWN OF WHITESTOWN. ASPHALT PAVING OF THE MAIN ROAD LANES SHALL MEET THE MINIMUM REQUIREMENTS OF THE TOWN OF WHITESTOWN FOR ROADWAY PAVING, OR MATCH THE DEPTH OF EXISTING ASPHALT, WHICHEVER IS GREATER.

MILL EXISTING ROAD 1.5" DEEP A MINIMUM OF 10' BEYOND THE ROADWAY REPLACEMENT LIMITS AT EACH END. CONTINUE 1.5" HMA SURFACE PAVING OVER THE MILLED AREA TO PROVIDE A SMOOTH TRANSITION BETWEEN NEW AND EXISTING ASPHALT PAVEMENT. CURBING SHALL BE EXTENDED THE ENTIRE LENGTH OF THE ACCELERATION AND DECELERATION LANES. IMPROVEMENTS SHALL BE MADE AS NECESSARY TO PROVIDE APPROPRIATE DRAINAGE WHERE THE PASSING BLISTER IS CONSTRUCTED. ADDITIONAL RIGHT OF WAY SHALL BE ACQUIRED AS NECESSARY TO CONSTRUCT PROPER DRAINAGE IMPROVEMENTS AT PASSING BLISTER.

REQUIRED ON ALL ARTERIAL AND COLLECTOR STREETS AT THE TOWN'S DISCRETION.

ROADWAY IMPROVEMENTS AT NEW DEVELOPMENT ENTRANCES N.T.S.

A REGISTER Y

★ 11200431

STATE OF

STOWN TANDARD = WF SIGI OF OWN EET I T(STRI

