

BBC

Pump and Equipment Company, Inc.

June 8, 2022

To: Whitestown Utilities
Attn: Bill Johnson
Subject: Perryworth Lift Station Bases-Rails-Standpipe

Bill,

Thank you for the opportunity to submit pricing covering pumping equipment for the subject job.

Remove existing pump bases, guide rails, upper guide brackets, standpipe, cross over elbows in wet well. Install new Hydromatic 6" MTM base elbows, new stainless steel guide rails, new stainless steel upper guide rail brackets, new 6" ductile iron standpipe, new 6" cross over elbows. Confined space entry, Hilti stainless steel anchors and Hilti adhesive sticks. Labor (2 men) and a crane truck.

Total for above equipment and labor.....\$12,793.00

Above price does not include vac/pump truck and/or bypass pumping. Wet well cleaning and bypass is to be provided by customer.

The above price is net to you, delivered to the jobsite with freight allowed. Delivery from factory is 4 to 6 weeks. Price is firm through quoted shipping cycle based on an order being received within thirty days of quotation date. No sales and/or use taxes are included. Terms are Net 30 days.

We hope you find our proposal acceptable. Should you have any questions, please contact us.

Respectfully,

Dave Dunnuck
Sales